

**ADHOC REPAIR AND PREVENTIVE MAINTENANCE OF HI-LIFT AIR-CONDITIONING SYSTEMS
FOR PERIOD 1 JUL 2021 TO 30 JUN 2024 (WITH AN OPTION FOR TWO MORE YEARS)**

SCOPE OF WORK AND PRICE SUBMISSION TABLE

A 6 Monthly Work Scope For Vanbody Air-Conditioning Systems

1	Greasing of bearing, cleaning and washing of dirt at the wheel fan;
2	Remove and install of the evaporator and condenser coils for chemical cleaning;
3	Inspect & service air-con compressor;
4	Adjust air-con belting;
5	General cleaning of air filter of the air-con blower;
6	General flushing the system with R141B and nitrogen;
7	Vacuum the system;
8	Recharge the system with refrigerant;
9	Test pressure and check leakage; and
10	Receive drier or desiccant;
11	Expansion valve;
12	Compressor oil; and
13	Fan belt.

B Vendor to state the price per unit per 6 months of the above work scope:

S/N	AIR-CON BRAND MODEL	Equipment use on	NO. OF VEHICLES	RATE PER 6-MONTHLY PM PER VEHICLE (\$)				
				01.07.21 - 30.06.22	01.07.22 - 30.06.23	01.07.23 - 30.06.24	1st Option Year 01.07.24 - 30.06.25	2nd Option Year 01.07.25 - 30.06.26
1	Mitsubishi TD43C/TD60	Catering Hi-lifts	5					
2	Carrier Xarios 500	Catering Hi-lifts	5					
3	Carrier Xarios 600	Catering Hi-lifts	51					
4	Sutrack Sandan 510	Ambulift	4					
5	Thermo king V700	Catering Hi-lifts	40					
6	Thermo king SV 800	Catering Hi-lifts	2					
7	Thermo king with independent Engine UT1200	Catering Hi-lifts	3					
		Total	110					

C MANHOUR RATE FOR ADHOC AIRCON PROJECT WORK FOR BOTH DRIVER'S CABIN AND VANBODY

S/N	MANHOUR RATE FOR ADHOC AIRCON PROJECT WORK				
	01.07.21 - 30.06.22	01.07.22 - 30.06.23	01.07.23 - 30.06.24	1st Option Year 01.07.24 - 30.06.25	2nd Option Year 01.07.25 - 30.06.26
1					