

This Tender (RFx CW2206Q438) consists of Three section/s §:

§A. SICC2 replace existing defective cable. 2 NOS. @ L2 Outbound Crawford Dr#11

§B. SICC1 replace Secomak GB5403 gas booster pumps; 2 Units

§C. SICC1 replace fiberglass insulation and Reducer Collars

An interested Vendor may bid (make an offer) for any of the above Three divided § sections/projects, or may also bid (submit quotation) for all 3 identified § sections (A), (B) & (C) together.

For **Site Show Round, Operational & Technical Queries**: pls write in for an assigned slot in our efforts to reduce group gathering size and to follow prevailing guidelines.

Location address1: 20 Airport Blvd. Singapore 819659

Location address2: 30 Changi North Crescent, Singapore 499612

Name of Contact Point: **Alvin Tan** <Alvin_Tan@sats.com.sg>

POC Mobile: 98467620

§A. SICC2 replace faulty CABLE FOR L2 OUTBOUND CRAWFORD DOOR 11

SICC2 Level 2 Outbound 11 - Replacement of existing defective cable
BM/SICC2/202205/000384

SICC2 Level 2 Outbound 11
Replacement of existing defective cable
BM/SICC2/202205/000384
Before



§B. SICC2 replace Secomak GB5403 gas booster pumps; 2 Units.

SCOPE OF WORKS/SPECIFICATION/REQUIREMENTS

1. Supply labour, tools & materials to replace 1 sets of Secomak GB5403 gas booster pump, 400 volts / 3 phase / 50 Hz including the dismantling & removal of existing
2. Airfreight charge for 2 units gas boostere pump

§C. SICC1 replace fiberglass insulation and Reducer Collars

Scope

- 1) Supply skill labour and material to dismantle and disposal existing worn off fiberglass insulation with aluminum foil & proper scrape and clean the aircon main duct surface.
- 2) Supply skill labour and material to insulate Amarflex or K-flex 13mm & Galvanized bracket replacement works with all kind of necessary accessory.
 - i) Duct size 2000mm X 850mm - 5 meter run (Bracket - 2 pairs)
 - ii) Duct size 500mm X 400mm - 9 meter run (Bracket - 3 pairs)
 - iii) Duct size 400mm X 400mm - 6.5 meter run (Bracket - 4 pairs).
 - iv) Duct size 300mm X 300mm - 4 meter run (Bracket - 2 pairs).
- 3) Supply skill labour and material to dismantle and disposal (6 Nos) existing Reducer Collars duct facing side & proper seal up with galvanized steel.
- 4) Supply skill labour and material to install New Rigid Duct collars with Amarflex insulation with Removable double deflection diffuser 600mm X 600mm - 6 nos

Dimantle & disposal of worn-off insulations

Amarflex insulation

2000mm X 850mm M²

500mm X 400mm M²

400mm X 400mm M²

300mm X 300mm M²

Dismantle & disposal of worn-off Reducer Collars

New Rigid Duct collars with Amarflex insulation